

Strengthening Audit Oversight of Public Private Partnerships

Case Study on Street Lighting National Programme (SLNP) of
Energy Efficiency Services Limited (EESL)

A Scalable Public–Private Partnership (PPP) Model

Sector Context and PPP Rationale – Street Lighting



➤ Brief Overview of the Sector & Its Evolution under PPPs

- Street lighting is a **core urban public service**, essential for safety, mobility, and law & order.
- The sector involves **large asset base**, high energy consumption, and continuous O&M requirements
- Historically delivered through **ULB-owned assets and utility power supply**, with limited performance accountability
- Increasing focus on **energy efficiency, service quality, and lifecycle cost optimization** led to adoption of PPP/ESCO approaches.

➤ Why PPP Was Chosen over EPC / Traditional Procurement

- EPC models required high upfront capital expenditure by ULBs and did not ensure long-term O&M quality.
- Traditional procurement separated installation from maintenance, leading to asset deterioration over time.
- PPP enabled: No upfront capex for ULBs, Lifecycle responsibility (install–operate–maintain) with a single entity, Performance-linked payments instead of asset-based payments
- Risk transfer of technology, performance, and O&M to the private/implementing entity.

➤ Typical models include:

- **Energy Service Company (annuity – Cost Plus / savings-linked), Design Build Operate Maintain, and performance-based O&M contracts.**

Street Lighting National Programme (SLNP): Overview

- Hon'ble Prime Minister, on **5th January 2015** launched the SLNP to replace conventional Street Lights with smart and energy efficient LED streetlights.
- EESL (ESCO) was appointed as a nodal agency from Ministry of Power. EESL is a joint venture of four PSUs, NTPC, Power Grid, REC & PFC.
- An **ESCO** is an entity that **designs, finances, implements, and maintains energy-efficiency projects**, and **recovers its investment from the energy savings achieved**, rather than through upfront payment by the public authority.
- Implemented at scale across States in ULBs and Gram Panchayats
- Programme designed with no upfront capital expenditure for ULBs and long-term service contracts.
- National scale makes SLNP systemically important from an audit and oversight perspective
- Impact: Enhances public safety, reduces energy costs, and lowers carbon emissions

• Progress Till Date:



No. of Street Lights installed
- 1.34 crore



Capacity generation avoided
- 1,505 MW



Annual Energy Saving
- 9.03 billion kWh




Total no. of ULB.s completed
- 1559

• The dashboard :

- ✓ Gives an insight into the no. of streetlights replaced across the country
- ✓ Country wide additional information on realization of- Total energy savings, Carbon emission reduction, and Peak demand avoidance

- Adopting “smart LED lights” deployment: “Smart Lights” connected through a web- based monitoring system enabling remote operations and efficient use of energy.



SLNP Dashboard

(<https://slnp.eeslindia.org/>)



SLNP as a Public – Private Partnership (PPP) Model

- Public Partner (Urban Local Body, Gram Panchayat /State Government)
 - Provides project area and approvals
 - Pays monthly charges from **deemed energy savings**, procurement & maintenance cost over a defined contract period.

- Private Partner (EESL – ESCO):
 - Invests upfront capital
 - Procures, installs, operates & maintains LED streetlights
 - Bears technology, performance & maintenance risks.

- Outcome:
 - No upfront capex for ULBs
 - Guaranteed service levels & energy savings
 - Simple, transparent, long-term sustainable urban infrastructure

SLNP: Benefits to Stakeholders

Municipalities:

- Reduced energy bills
- Improved streetlight infrastructure

EESL:

- Scale of operations and cost recovery

Public:

- Safer, well-lit streets
- Environmental benefits through reduced emissions

SLNP: Implementation Process

- Survey and Design: Assess existing streetlight infrastructure for baseline.
- Proposal: Develop a financing and implementation plan (ESCO/Annuity model – Cost Plus).
- Installation: Replace conventional streetlights with LEDs.
- Monitoring & Maintenance: Ensure performance and optimize savings.
- Savings Sharing: Municipalities repay based on energy savings, Procurement & maintenance cost

KPI for Service Delivery

- **Luminaire Availability (%)**
Percentage of streetlights operational at any given time (typically $\geq 95\%$).
- **Deemed Energy Savings (%)**
Energy Savings due to usage of energy efficient luminaire and components. (typically, ~ 40 to 60%)
- **Fault Rectification Time (TAT)**
Average time taken to repair/replace failed lights (e.g., 24–72 hours).
- **Lighting Performance Standards**
Compliance with illumination levels (National Lighting Code), uniformity, and glare norms as per approved standards.
- **Monitoring & Reporting Compliance**
Accuracy and timeliness of data from the centralized control and monitoring system (CCMS), including outage reporting and savings verification.

Demand, Technology, and Design Assumptions

- **Demand Assumptions**

Street lighting demand is largely **stable and non-discretionary**, linked to existing road length, number of poles, and standard operating hours (dusk-to-dawn).

- **Energy Consumption**

Baseline established based on survey which includes existing fixture wattage, burning hours, and historical utility bills, forming the basis for deemed energy savings.

- **Technology Assumptions**

LED luminaires assumed to deliver 40–60% energy savings, longer life (50,000+ hours), and lower failure rates compared to conventional lights.

- **Design & Standardization**

Standardized luminaire designs selected based on road category, mounting height, and spacing, ensuring compliance with lighting and safety norms.

- **Smart Controls & Monitoring**

Assumption of reliable operation of centralized control and monitoring systems (CCMS) for remote switching, fault detection, dimming, and performance measurement.

Commercial Risk Drivers

- Budgeting by UDD/ULB not sufficient

- ULBs/UDD not honouring their contractual part of the agreement
 - Opening of Payment Security Mechanism.
 - Payments within 30 days of invoicing.
 - Delayed/Late payment surcharge.
 - UDD/State Admin. Undermining State govt. assurance/ responsibility.

- Non-Payments over a prolonged period with ageing up to 03 years or more
 - The payments even does not cover debt, equity & tax repayments leave alone O&M payments.
 - Non payments to O&M vendors which are mainly MSME vendors, effects O&M services.
 - Material adverse impact on EESL
 - Additional borrowing, which is a financial strain on EESL.

Technical Risk Drivers

- **Technology Performance Risk (Technical)**
Risk of LED luminaires or control systems not achieving expected life, illumination levels, or energy savings.
- **O&M and Asset Reliability Risk (Technical)**
Higher-than-expected failure rates, vandalism, or delayed fault rectification affecting service availability KPIs.
- **Integration & System Risk (Technical)**
Challenges in integrating CCMS, smart controls, and utility metering systems across diverse urban environments.

International and India Best Practices - PPPs in Street Lighting



➤ Relevant Global Benchmarks:

- United Kingdom (Birmingham City Council), USA (Los Angeles), and Brazil (São Paulo) have implemented long-tenure ESCO / DBOM street-lighting PPPs with independent, actual M&V and utility- or ring-fenced revenue-backed payment mechanisms, resulting in improved bankability, payment certainty, and service performance.

➤ Practices Improving Bankability & Performance:

- Strong payment security (escrow / utility deductions)
- Performance-Linked Payments
- Standardized Specifications & Contracts
- Centralized Monitoring Systems
- Risk Allocation to Best-Placed Party
- Independent Verification & Transparency

➤ Indian PPP Practice (SLNP Context):

- India adopted a scaled ESCO model with centralized implementation; however, **payment security relies heavily on ULB/State budget discipline** rather than automatic deduction mechanisms.

➤ Key Difference vs Global Models:

- Global PPPs ensure **predictable cash flows and enforceable payment mechanisms**, whereas Indian PPPs face **institutional payment risk**, delayed budgets, and weaker enforcement of state assurances.

Design, Technology, and Innovation Aspects

➤ Role of Technology in Improving Service Delivery & Efficiency

- High-efficacy LED luminaires and **CCMS-based smart controls** improve energy efficiency, illumination quality, and service reliability.
- **Data-driven O&M** enables proactive maintenance, reducing downtime and lifecycle costs.

➤ Contractual Flexibility

- **Standardized yet flexible designs** allow adjustment of wattage, optics, and spacing based on road conditions.
- **Future-ready architecture** supports technology upgrades and smart-city integration without major contract changes.

➤ Risks of Rigid Specifications

- **Restrict adoption of improved LED technologies** during the contract period.
- **sub-optimal illumination or energy outcomes** under varying local conditions
- **higher lifecycle costs** and reduced performance efficiency.
- **discourage innovation** and limit scalability with evolving urban infrastructure needs.

Common Failure Points in PPP Structuring

- **Weak Baseline Assessment**
 - Inadequate or inaccurate baseline data on existing fixtures, burning hours, and energy consumption leading to disputes on deemed savings.
- **Over-Optimistic Savings Assumptions**
 - Aggressive assumptions on energy savings and failure rates without adequate sensitivity analysis.
- **Misalignment between Contract Design and Ground Realities**
 - **Payment Security Gaps**
Absence or weak enforcement of payment security mechanisms, resulting in delayed or irregular annuity payments by ULBs.
 - **Poor Risk Allocation**
Transfer of policy or payment risks to the private partner, despite limited control, affecting project bankability.
 - **Insufficient Contractual Clarity**
Ambiguity in O&M scope, replacement obligations, KPI definitions, and penalties leading to interpretation disputes during execution.

Regulatory and Policy Bottlenecks

➤ Policy Uncertainty / Frequent Changes

- Lack of uniform policy adoption across States/ULB, on ownership, metering, and payment responsibility.
- Tariff and billing policy uncertainty, affecting deemed savings calculations
- Weak enforcement of State guarantees / tripartite agreements, reducing credibility of policy assurances

➤ Approval & Clearance Delays

- Delays in budget approvals and fund releases, impacting timely annuity payments.
- Approval and clearance constraints
- Implementation delays and cost escalation

➤ Impact on Project Viability

- Cash flows and financial sustainability of projects
- Mismatch between contractual timelines and actual execution.
- Uncertain payment and enforcement environment

Data, Monitoring, and Performance Metrics

- Availability & Reliability of Data
 - Performance assessment depends on the accuracy of:
 - ✓ baseline data
 - ✓ meter readings
 - ✓ CCMS system logs

- Monitoring & Reporting Quality
 - Centralized CCMS enables:
 - ✓ real-time monitoring
 - ✓ KPI-based reporting of availability
 - ✓ faults, energy use
 - ✓ Supports illumination compliance

- Certification & Verification Issues
 - **Independent / joint verification** of infrastructure and service levels is required before release of payments.
 - Verification is based on **CCMS data, field inspections, and baseline records**
 - **Robust MIS and audit trails** are necessary to link performance certification with payments

Relevance for Audit and Oversight

➤ **Typical Areas Where Audits Find Weaknesses**

- Non-compliance with contractual KPIs for
 - ✓ Availability
 - ✓ fault rectification timelines
 - ✓ service standards
- Payment security and annuity disbursement gaps
 - ✓ including delayed payments
 - ✓ weak enforcement of contractual safeguards

➤ **Indicators of Stress or Under-Performance**

- Persistent payment delays and receivable ageing
- Mismatch in risk allocation
 - ✓ Payment or policy risks placed on entities that cannot control payments or approvals
 - ✓ Responsibility not aligned with actual control, leading to delays and disputes

➤ **Importance of Documentation & Traceability**

- Integrity of MIS, certifications, and approvals is critical for
 - ✓ establish linkage between performance, payments, and accountability
- Complete audit trail (contracts, KPIs, certifications, payment records) for
 - ✓ transparency and defensible audit conclusions

Recommendations for Future PPPs

- **Strengthen Baseline & DPR Quality**
Ensure robust baseline assessments, independent validation, and realistic savings assumptions before contract award.
- **Enhance Payment Security Mechanisms**
Mandate escrow accounts, state guarantees, or utility-backed deductions to reduce payment default risks.
- **Standardize KPIs & Data Protocols**
Adopt uniform KPI definitions, CCMS standards, and reporting formats across states to improve comparability and auditability.
- **Improve Risk Allocation & Contract Clarity**
Align risks with the party best placed to manage them, with clear provisions on O&M, replacements, penalties, and force majeure.
- **Enable Innovation with Safeguards**
Allow adoption of new technologies (adaptive lighting, analytics) while maintaining flexibility and safeguards against performance dilution.